56

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI
Office of the Executive Engineer, Dasarahalli Division

SCHEDULE-B

Name of Work :- Removal of debris & desilting of drains in Bagalagunte in ward no. 14

Sl.No	Description of work	Unit	Qty	Sanctioned Rate	
				Rate	Amount
1	2	3	4	5	6
1	Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqmt	1994.40	68.67	Sixty Eight and Sixty Seven Paise
2	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m	Cum	6665.40	223.70	Two Hundred Twenty Three and Seventy Paise
3	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqmt	1994.40	84.18	Eighty Four and Eighteen Paise
4	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Days	40.00	7021.73	Seven Thousand Twenty One and Seventy Three Paise
5	Tractor 50 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the wor	Days	160.00	2624.79	Two Thousand Six Hundred TwentyFour and Seventy Nine Paise

M N Ramesh

Signature of Contractors

Exicutive Engineer
Dasarahalli Zone